

# LM8M64 Color STN LCD Module

(Model Number: LM8M64)

# **Specifications**

Spec No.: LC98109A

Dated: May 31. 2002

### **NOTICE**

This publication is the proprietary of SHARP and is copyrighted, with all rights reserved. Under the copyright laws, no part of this publication may be reproduced or transmitted in any form or by any means, electronic or mechanical for any purpose, in whole or in part, without the express written permission of SHARP. Express written permission is also required before any use of this publication may be made by a third party.

The application circuit examples in this publication are provided to explain the representative applications of SHARP's devices and are not intended to guarantee any circuit design or permit any industrial property right or other rights to be executed. SHARP takes no responsibility for any problems related to any industrial property right or a third party resulting from the use of SHARP's devices, except for those resulting directly from device manufacturing processes.

In the absence of confirmation by device specification sheets, SHARP takes no responsibility for any defects that occur in equipment using any of SHARP's devices, shown in catalogs, data books, etc. Contact SHARP in order to obtain the latest device specification sheets before using any SHARP's device.

SHARP reserves the right to make changes in the specifications, characteristics, data, materials, structures and other contents described herein at any time without notice in order to improve design or reliability. Contact SHARP in order to obtain the latest specification sheets before using any SHARP's device. Manufacturing locations are also subject to change without notice.

Observe the following points when using any device in this publication. SHARP takes no responsibility for damage caused by improper use of the devices.

The devices in this publication are designed for use in general electronic equipment designs, such as:

- · Automotive auxiliary information display
- · Automotive audio visual equipment

The appropriate design measures should be taken to ensure reliability and safety when SHARP's devices are used for equipment such as:

- Transportation control and safety equipment(i.e., aircraft, trains, automobiles, etc.)
- · Traffic signals
- · Gas leakage sensor breakers
- · Alarm equipment
- · Various safety devices etc.

SHARP's devices shall not be used for equipment that requires extremely high level of reliability, such as:

- Military and space applications
- · Nuclear power control equipment
- · Medical equipment for life support

Contact a SHARP representative, in advance, when intending to use SHARP's devices for any "specific" applications other than those recommended by SHARP.

Contact and consult with a SHARP representative if there are any questions about the contents of this publication.

PREPARED BY:	DATE		SPEC No. LC98109A
		SHARP	FILE No.
			ISSUE NOV. 27.1998
APPROVED BY:	DATE	LIQUID CRYSTAL DISPLAY GROUD SHARP CORPORATION	
		SPECIFICATION	REPREZENTATIVE DIVISION  ENGINEERING DEPARTMENT 1  DUTY LCD DEVELOPMENT  CENTER  DUTY LIQUID CRYSTAL  DISPLAY GROUP
	Mo	DEVICE SPECIFICATION fo Passive Matrix Color LCD Mode (640×240 dots) odel No. LM8M64	•
□CUSTON <u>DATE</u> BY	MER'S APPR		SENTED
			(1 Inoue
		BY Y.In	
		DIV	ISION GENERAL MANAGER TY LCD DEVELOPMENT CENTER

DUTY LIQUID CRYSTAL DISPLAY GROUP

SHARP CORPORATION /



	DOC.FIRST ISSU JAN.28.1998			
DATE	REF.PAGE PARAGRAPH DRAWING No.	REVISED NO.	SUMMARY	CHECK AND APPROVAL
1998.11.27	P17	À	Optical Characteristics Contrast ratio	J Inone
- Aut. Mar				
<del></del>				
			<del></del>	
· - · · · · · · · · · · · · · · · · · ·				



SPEC No.	MODEL	No.	PAGE
LC98109A		LM8M64	1

# OPrecautions

1) Industrial(Mechanical) design of the product in which this LCD module will be incorporated must be made so that the viewing angle characteristics of the LCD may be optimized.

This module's viewing angle is illustrated in Fig.1.

 $\theta$  y MIN. < viewing angle <  $\theta$  y MAX.

(For the specific values of  $\theta$  y MIN., and  $\theta$  y MAX., refer to the table9)

Please consider the optimum viewing conditions according to the purpose when installing the module.




Fig.1 Definition of viewing angle

2) When installing the module, pay attention and handle carefully not to allow any undue stress such as twist

bend.

- 3) Since the front polarizer is easily damaged. Please pay attention not to scratch on its face. It is recommended to use a transparent acrylic resin board or other type of protective panel on the surface of the LCD module to protect the polarizer, LCD panel, etc..
- 4) If the surface of the LCD panel is required to be cleaned, wipe it swiftly with cotton or other soft cloth. If it is not still clear completely, blow on and wipe it.
- 5) Water droplets, etc. must be wiped off immediately since they may cause color changes, staining, etc., if it remained for a long time.
- 6) Since LCD is made of glass substrate, dropping the module or banging it against hard objects may cause cracking or fragmentation.
- 7) Since CMOS LSIs are equipped in this module, following countermeasures must be taken to avoid electrostatics charge.

or

SPEC No.	MODEL	No.	PAGE
LC98109A		LM8M64	2

# 1. Operator

Electrostatic shielding clothes shall be had because it is feared that the static electricity is electrified to human body in case that operator have a insulating garment.

# 2. Equipment

There is a possibility that the static electricity is charged to equipment which have a function of peeling or mechanism of friction(EX: Conveyer, soldering iron, working table), so the countermeasure countermeasure(electrostaticearth:  $1 \times 10^8 \,\Omega$ ) should be made.

# 3.Floor

Floor is a important part to leak static electricity which is generated from human body or equipment. There is a possibility that the static electricity is charged to them without leakage in case of insulating floor, so the countermeasure(electrostatic earth:  $1 \times 10^8 \Omega$ ) should be made.

# 4. Humidity

Humidity of working room may lower electrostatics generating material's resistance and have something to prevent electrifying. So, humidity should be kept over 50% because humidity less than 50 % may increase material's electrostatic earth resistance and it become easy to electrify.

# 5. Transportation/storage

The measure should be made for storage materials because there is a possibility that the static electricity, which electrify to human body or storage materials like container by friction or peeling, cause the dielectric charge.

# 6. Others

The laminator is attached on the surface of LCD module to prevent from scratches, fouling and dust. It should be peeled off unhurriedly with using static eliminator.

And also, static eliminator should be installed to prevent LCD module from electrifying at assembling line.


- 8) Don't use any materials which emit gas from epoxy resin(amines' hardener) and silicon adhesive agent(dealcohol or deoxym) to prevent change polorizer color owing to gas.
- 9) Since leakage current, which may be caused by routing of CCFT cables, etc., may affect the brightness of display, the inverter has to be designed taking the leakage current into consideration. Thorough evaluation of the LCD module/inverter built into its host equipment shall be conducted, therefore, to ensure the specified brightness.
- 10) Avoid to expose the module to the direct sun-light, strong ultraviolet light, etc. for a long time.
- 11) If stored at temperatures under specified storage temperature, the LC may freeze and be deteriorated. If storage temperature exceed the specified rating, the molecular orientation of the LC may change to that of a liquid, and they may not revert to their original state. Therefore, the module should be always stored at normal room temperature.
- 12) Disassembling the LCD module can cause permanent damage and should be strictly avoided.

13) Procedure insert mating connector

When the mating connector is inserted, it should be parallel to the used connector of LCD module and it should be inserted horizontally.

When the mating connector is attempted to be fixed to LCD connector, it should be inserted properly in order not to create a gap as shown "A".

Please insert the connector as both edge is placed to the connect position of LCD connector.



- 14) This specification describes display quality in case of no gray scale. Since display quality can be affected by gray scale methods, display quality shall be carefully evaluated for the usability of LCD module in case gray scale is displayed on the LCD module.
- 15) The module should be driven according to the specified ratings to avoid permanent damage.

  DC voltage drive leads to rapid deterioration of LC, so ensure that the drive is alternating waveform by continuous application of the signal M. Especially the power ON/OFF sequence shown on Page 24 should be kept to avoid latch-up of drive LSIs and application of DC voltage to LCD panel.

Page		
5		
6		
7		
8		
10		
11		
12		
13		
14		
15		
17		
I 18		
Ⅱ 19		
20		
21		
22		
23		
24		
	5 6 7 8 10 11 12 13 14 15 17 I 18 II 19 20 21 22	5 6 6 7 8 10 11 12 13 14 15 17 1 18 II 19 20 21 22 23



SPEC No.	MODEL	No.	PAGE
LC98109A		LM8M64	5

# 1.Application

This data sheet is to introduce the specification of LM8M64, passive Matrix type Color LCD module.

# 2. Construction and Outline

Construction: 640×240 dots color display module consisting of an LCD panel, PWB(printed wiring board) with electric components mounted onto, TCP(tape carrier package) to connect the LCD panel and PWB electrically, and plastic chassis with CCFT back light and bezel to fix them mechanically. Signal ground(Vss) is connected with the metal bezel.




Fig.2 Module structure

Outline :See Fig. 16

DC/DC converter is built in.

Connection :See Fig. 16, Table 6 and Table 7

The LCD module shall meet the following inspection standard: S-U-035

SPEC No.	MODEL No.	PAGE
LC98109A	LM8M64	6

# 3. Mechanical Specification

# Table1

Parameter	Specifications	Unit
Outline dimensions	$225.4(W) \times 87.4(H) \times 7.0MAX(D)$	mm
Active area	191.98(W)×71.98(H)	mm
Display format	640(W)×240(H)	-
Dot size	$0.08 \times RGB(W) \times 0.28(H)$	mm
Dot spacing	0.02	mm
Base color *1	Normally black *2	-
Weight	Approx.175	g

- \*1 Due to the characteristics of the LC material, the colors vary with environmental temperature.
- \*2 Negative-type display

Display data "H" : ON  $\rightarrow$  transmission Display data "L" : OFF  $\rightarrow$  light isolation

# 4. Absolute Maximum Ratings

4-1. Electrical absolute maximum ratings

Table 2

Parameter	Symbol	MIN.	MAX.	Unit	Remark
Supply voltage(Logic)	$V_{ m DD}$ - $V_{ m SS}$	0	6.0	V	Ta=25 ℃
Input voltage	V <sub>IN</sub>	-0.3	V <sub>DD</sub> +0.3	V	Ta=25 °C
Vcon voltage	Vcon	0	$V_{ m DD}$	V	Ta=25 °C

SPEC No.	MODEL	No.	PAGE
LC98109A		LM8M64	7

# 4-2. Environment Conditions

# Table 3

14010-5					
Item	Ts	stg	T	opr	Remark
Item	MIN.	MAX.	MIN.	MAX.	Kemark
Ambient temperature	-25 °C	+60 °C	0 ℃	+40°C	Note 4)
Humidity	Note 1)		No	te 1)	No condensation
Vibration	Note 2)		No	te 2)	3 directions(X/Y/Z)
Shock	Note 3)		No	te 3)	6 directions( $\pm X \pm Y \pm Z$ )

Note 1) Ta≤40 °C......95 % RH Max.

Ta>40 °C......Absolute humidity shall be less than Ta=40 °C/95 % RH.

# Note 2)

# Table 4

Frequency	10 Hz∼57 Hz	57 Hz∼500 Hz
Vibration level	-	$9.8 \text{ m/s}^2$
Vibration width	0.075 mm	-
Interval	10 Hz∼500 Hz	~10 Hz/11.0 min

2 hours for each direction of X/Y/Z (6 hours as total)

Note 3) Acceleration : 490 m/s<sup>2</sup>

Pulse width : 11 ms

3 times for each directions of  $\pm X/\pm Y/\pm Z$ 

Note 4) Care should be taken so that the LCD module may not be subjected to the temperature out of this specification.

- 5. Electrical Specifications
- 5-1. Electrical characteristics

Table 5 Ta=25 °C VDD= $3.3 \text{ V} \pm 10 \%$ 1/tFRM=90 Hz								
Parameter	Symbol	Con	Min.	Тур.	Max.	Unit		
Supply voltage (Logic)	$V_{DD}$ - $V_{SS}$	$Ta = 0 \sim 40 \text{ °C (Note 1)}$		3.0	3.3	3.6	V	
Contrast adjust voltage (Note 4)	Vcon -V <sub>SS</sub>	Ta = 0∼40 °C		0.8	1.95	2.8	V	
Input signal voltage	$V_{\rm IN}$	"H" level	$Ta = 0 \sim 40$ °C	$0.8V_{\mathrm{DD}}$	-	$V_{ m DD}$	V	
		"L" level		0	-	$0.2V_{\mathrm{DD}}$	V	
Supply ourrant	I <sub>DD</sub> 1(TYP.)	Ta =25 $^{\circ}$ C(Note 1,2)		-	22	33	mA	
Supply current	I <sub>DD</sub> 2(MAX.)	Ta=25 °C(Note1,3)		-	32	48	mA	
Rush current (Logic)	Irush	Ta =25 °C (Note 1)			100mA	×50ms		
Ripple current (Logic)	Irip	Ta =25 °C (Note 1)			50mA×	150 μ s		
Power consumption	Pd1(TYP)	No	ote 2)	-	73	109	mW	
rower consumption	Pd2(MAX)	No	ote 3)	-	105	158	mW	

Note 1) Under the following conditions.;

① Immediately after the rise of  $V_{DD}$  . :100mA $\times$ 50ms

② Under the situation that DISP signal is on and kept steady  $: 50 \text{mA} \times 150 \,\mu \text{ s}$ 

Note 2) Frame frequency = 90 Hz, Vcon - Vss =max contrast voltage
Display pattern = all digits ON (D0-7 = "H")
Note 2) Frame fraguency = 00 Hz, Veen, Vee = may contract voltage
Note 3) Frame frequency = $90 \text{ Hz}$ , Vcon - Vss = max contrast voltage
Display pattern = 1bit checker
Display pattern = 1bit checker
Display pattern = 1bit checker
Display pattern = 1bit checker



SPEC No.	MODEL	No.	PAGE
LC98109A		LM8M64	9

Note 4) Contrast adjust voltage "Vcon-Vss" is transformed into the LCD driving voltage " $V_{LCD}$ " by following circuit built in the LCD module.

# 

Fig.3 Voltage generator for optimum contrast

SPEC No. MODEL No. PAGE

LC98109A LM8M64

10

# 5-2.Interface signals

OLCD <u>Table 6</u>

Pin No.	Symbol	Description	Level
1	YD	Scan start-up signal	"H"
2	VSS	Ground potential	-
3	LP	Input data latch signal	"H" → "L"
4	VSS	Ground potential	-
5	XCK	Shift clock for input data	"H" → "L"
6	VSS	Ground potential	-
7	DISP	Display control signal	H(ON), L(OFF)
8	VDD	Power supply for logic(3.3v)	-
9	Vcon	Contrast adjustment voltage	-
10	VSS	Ground potential	-
11	D0	Display data signal	H(ON), L(OFF)
12	D1	Display data signal	H(ON), L(OFF)
13	D2	Display data signal	H(ON), L(OFF)
14	D3	Display data signal	H(ON), L(OFF)
15	VSS	Ground potential	-
16	D4	Display data signal	H(ON), L(OFF)
17	D5	Display data signal	H(ON), L(OFF)
18	D6	Display data signal	H(ON), L(OFF)
19	D7	Display data signal	H(ON), L(OFF)
20	VDD	Power supply for logic(3.3v)	-

OCCFT Table7

Pin No	Symbol	Description	Level
1	VL1(HV)	High voltage line (from Inverter)	1
2	NC	NC	-
3	VL2(GND)	Ground line (from Inverter)	-

# 5-3. Connectors

 $\bigcirc LCD$ 

Used connector: FH12-20S-0.5SH(HIROSE)


Correspondable connector: FFC-CONNECTOR(0.5mm pitch 20pin)


 $\bigcirc$ CCFT

Used connector :HV-2S-C1(JAE)

Correspondable connector :HV-2P-HF-E1400(JAE)

Except above connector shall be out of guaranty.





SHARP	SPEC No. <b>LC98109A</b>	MODEL No.  LM8M64	PAGE 13
YD LP	t <sub>FRM</sub>	t <sub>LYH</sub>	t WLPH
LP t <sub>ls</sub>	t <sub>r</sub>	t <sub>CK</sub> t <sub>WCKH</sub> t <sub>WCKL</sub>	t <sub>DH</sub>
D0~7	$V_{IH} = 0$ $V_{IL} = 0$	0.8 V <sub>DD</sub> 0.2 V <sub>DD</sub>	

Fig.6 Interface timing chart

 SPEC No.
 MODEL No.
 PAGE

 LC98109A
 LM8M64
 14

# Table 8 Interface timing ratings

Ta=25 °C, VDD=3.3 V $\pm$ 10 %

Itama	Crumb of		Rating		I Imit
Item	Symbol	MIN.	TYP.	MAX.	Unit
Frame cycle *2,*3	$t_{FRM}$	8.33		16.94	ms
XCK signal clock cycle	$t_{CK}$	82			ns
"H" level clock width	$t_{ m WCKH}$	30			ns
"L" level clock width	$t_{WCKL}$	30			ns
LP signal "H" level pulse width	$t_{\mathrm{WLPH}}$	350			ns
Data set up time	$t_{\rm DS}$	25			ns
hold time	$t_{\mathrm{DH}}$	30			ns
YD signal "H" level set up time	$t_{ m HYS}$	125			ns
"H" level hold time	$t_{ m HYH}$	125			ns
"L" level set up time	$t_{ m LYS}$	100			ns
"L" level hold time	$t_{ m LYH}$	100			ns
LP ↑ allowance time from XCK ↓	$t_{ m LS}$			5	ns
LP ↓ allowance time from XCK ↑	$t_{ m LH}$	0			ns
Input signal rise/fall time *1	$t_r, t_f$			20	ns

- \*1 When LCD module is operated by high speed of XCK(Shift clock),  $(t_{CK} t_{WCKH} t_{WCKL})/2$  is maximum.
- \*2 LCD module functions at the minimum frame cycle of 8.33 ms(Maximum frame frequency of 120 Hz). Owing to the characteristics of LCD module, "shadowing" will become more eminent as frame frequency goes up, while flicker will be reduced.
- \*3 According to our experiments, frame cycle of 8.33 ms Min. or frame frequency of 120 Hz Max. will demonstrate optimum display quality in terms of flicker and "shadowing". But since judgment of display quality is subjective and display quality such as "shadowing" is pattern dependent, it is recommended that decision of frame frequency, to which power consumption of the LCD module is proportional, be made based on your own through testing on the LCD module with every possible patterns displayed on it
- $\frac{\text{The intervals of one LP fall and next must be always the same, and LPs must be input continuously.}}{\text{The intervals must be 70 <math>\mu$  s Max.}}

SPEC No.	MODEL	No.	PAGE	
LC98109A		LM8M64		15

# 6. Module Driving Method

# 6-1. Circuit configuration

Fig.12 shows the block diagram of the module's circuitry.

# 6-2. Display face configuration

The display consists of  $640 \times 3(R,G,B) \times 240$  dots as shown in Fig. 4.

The interface is single panel with double drive to be driven at 1/244duty ratio.

# 6-3. Input data and control signal

The LCD driver is 240 bits LSI, consisting of shift registers, latch circuits and LCD driver circuits. Input data for each row  $640 \times 3$  (R,G,B) will be sequentially transferred in the form of 8 bit parallel data through shift registers from top left of the display together with clock signal (XCK).

When input of one row  $640\times3$  (R,G,B) is completed, the data will be latched in the form of parallel data corresponding to the signal electrodes by the falling edge of latch signal (LP) then, the corresponding drive signals will be transmitted to the  $640\times3$  lines of column electrodes of the LCD panel by the LCD drive circuits.

At this time, scan start-up signal (YD) has been transferred from the scan signal driver to the 1st row of scan electrodes, and the contents of the data signals are displayed on the 1st row of the display face according to the combinations of voltages applied to the scan and signal electrodes of the LCD. While the data of 1st row are being displayed, the data of 2nd row are entered. When data for  $640 \times 3$  dots have been transferred, they will be latched by the falling edge of LP, switching the display to the 2nd row.

Such data input will be repeated up to the 244th row of each display segment, from upper row to lower rows, to complete one frame of display by time sharing method.

Then data input proceeds to the next display frame.

YD generates scan signal to drive horizontal electrodes.

Since DC voltage, if applied to LCD panel, causes chemical reaction in LC materials, causing deterioration of the materials, drive wave-form shall be inverted at every display frame to prevent the generation of such DC voltage.

Control signal M plays such a role.

Because of the characteristics of the CMOS driver LSI, the power consumption of the display module goes up with the clock frequency of XCK.

To minimize data transfer speed of XCK clock the LSI has the system of transferring 8 bit parallel data through the 8 lines of shift registers.

Thanks to this system the power consumption of the display module is minimized.

In this circuit configuration, 8 bit display data shall input to data input pins of D0-7.

Furthermore, the display module has bus line system for data input to minimize the power consumption with data input terminals of each driver LSI being activated only when relevant data input is fed.

Data input for column electrodes and chip select of driver LSI are made as follows:



| SPEC No. | MODEL No. | PAGE | | 16 | | |

The driver LSI at the left end of the display face is first selected, and the adjacent driver LSI right next side is selected when data of 240 dot (30XCK) is fed. This process is sequentially continued until data is fed to the driver LSI at the right end of the display face. This process is followed simultaneously both at the top and bottom column drivers LSI's.

Thus data input will be made through 8 bit bus line sequentially from the left end of the display face.

Since this display module contains no refresh RAM, it requires the above data and timing pulse inputs even for static display.

The timing chart of input signals are shown in fig. 6 and Table 8.

# 7.Optical Characteristics

1

Following spec are based upon the electrical measuring conditions, on which the contrast of perpendicular direction(  $\theta$  x =  $\theta$  y = 0  $^{\circ}$  ) will be MAX..

			<u>Ta</u>	<u>ble 9</u>	Ta =	= 25 °C,	$V_{DD} = 3.3V$	V, Vcon-	$V_{SS} = V_{max}$
Parame	eter	Symbol	Condition		MIN.	TYP.	MAX.	Unit	Remark
Vi avvin a an a	1	θx	Co>5.0 $\theta$ y = 0 °		-30	-	30		Mata 1)
Viewing ang	gie range	θу	C0>3.0	$\theta x = 0$ °	-15	-	25		Note 1)
Contrast	ratio	Co	$\theta x = \theta y = 0$ °		30	50	-	-	Note2)
Response	Rise	τr	$\theta x = \theta y = 0$		-	270	400	ms	Note3)
time	Decay	τd	$\theta \mathbf{x} = \theta$	$\theta x = \theta y = 0$ °		80	100	ms	Notes)
Module		X	$\theta x = \theta y = 0$ °		-	0.275	-	-	
chromaticit	White	у	$\theta \mathbf{x} = \theta$	y = 0 °	-	0.320	-	-	
y									

Note 1) The viewing angle range is defined as shown Fig.7.




Fig.7 Definition of Viewing Angle


Note 2) Contrast ratio is defined as follows:

 $Co = \frac{Luminance(brightness) \text{ all pixes "White" at Vmax}}{Luminance(brightness) \text{ all pixes "dark " at Vmax}}$ 

Vmax is defined in Fig.9.

Note 3) The response characteristics of photo-detector output are measured as shown in Fig.10, assuming that input signals are applied so as to select and deselect the dot to be measured, in the optical characteristics test method shown in Fig.8.

| SPEC No. | MODEL No. | PAGE | 18 |



Measuring Spot Size :  $\phi$  10 mm

 $\theta$  y: Angle from "normal" to viewing surface rotated about the vertical axis.

Fig. 8 Optical Characteristics Test Method I





Fig.9 Definition of Vmax

(Response Measurement)

Ta = 25 °C

In dark room


# TOPCON BM7 + quartz fiber



(Measuring spot size :  $\phi$  10 mm, Measuring Field : 2  $^{\circ}$  )

Fig. 10 Optical Characteristics Test Method II

PAGE SPEC No. MODEL No. 20 LC98109A LM8M64






Fig. 12 Circuit block diagram

LP -----

YD \_\_\_\_\_

XCK —

 $D0\sim D7$ 

**CCFT** 

Inverter

SPEC No. MODEL No. PAGE

LC98109A LM8M64 22

8. Characteristics of Backlight

The ratings are given on condition that the following conditions are satisfied.

8-1.Rating(Note)

 Note)
 Table 10

 Parameter
 MIN.
 TYP.
 MAX.
 Unit

 Brightness
 70
 80
 cd/m²

8-2.Measurement circuit: CXA-K0505-VJL(TDK) (at IL = 1.9mArms)

8-3. Measurement equipment: BM-7 (TOPCON Corporation)

8-4. Measurement conditions

1). Measurement circuit voltage: DC = 5.0 V, at primary side

2). LCD: All digits WHITE, VDD= 3.3 V, Vcon-VSS = Vmax, D0-7="H"(White)

Frame Frequency 90 Hz

3). Ambient temperature: 25 °C

Measurement shall be executed 30 minutes after turning on.

8-5.Used lamp: FAC1EX/207T2G1I/S/U(TOSHIBA LIGHTING&TECHNOLOGY CORP)

Used cable: UL3579,AWG#26 or UL3587,AWG#26

(NISSEI ELECTRIC CO.,LTD or SUMITOMO ELECTRIC INDUSTRIES LTD.)

(1)Rating (1pc)

Table11

Parameter	Symbol	MIN.	TYP.	MAX.	Unit	Remark
Lamp voltage	$V_{ m L}$	-	500	550	Vrms	
Lamp current	$I_{\mathrm{L}}$	-	1.9	2.0	mArms	*1
Lamp power consumption	$P_{\mathrm{L}}$	ı	0.95	1.05	W	*2
Lamp frequency	$F_{ m L}$	45	ı	100	kHz	-
Kick-off voltage	$V_{S}$	-	-	-	Vrms	Ta=25 °C
		-	-	1,300	Vrms	Ta=0 °C*3
Lamp life time	$L_{L}$	10 000	-	-	h	Ta=25 °C*4
						$I_L$ =2mArms

Within no conductor closed. (CCFT only)

- \*1 It is recommended that IL be not more than 2.0mArms so that heat radiation of CCFT backlight may least affect the display quality.
- \*2 Power consumption excluded inverter loss.
- \*3 The circuit voltage(VS) of the inverter should be designed to have some margin, because VS may be increased due to the leak current in case of the LCD module.
- \*4 Average life time of CCFT will be decreased when LCD is operating at lower and higher temperature.

SHARK	S	Н	A	R	P
-------	---	---	---	---	---

# (2)Operating life

The operating life time is 10 000 hours or more at 2.0 mA.

(Operating life with CXA-K0505-VJL or equivalent.)

The inverter should meet the following conditions to keep the specified life time of used lamp;


- -Since, symmetric waveform without spike in positive and negative
- -Output frequency range: 45 kHz-100 kHz

Make sure the operating conditions by executing the burn-in enough time.

The operating life time is defined as having ended when any of the following conditions occur;  $25\pm1^{\circ}$ C


- -When the voltage required for initial discharge has reached 110 % of the initials value.
- -When the illuminence quantity of light has decreased to 50 % of the initials value.

(NOTE) Rating are defined as the average brightness inside the viewing area specified in Fig. 13.



# 9.Lot Number

Lot number is shown at the position mentioned in Fig.14 in accordance with the following numbering rule.







Fig.15 Supply voltage sequence condition

	POWER ON	
Symbol	Allowable value	
a	0 ms MIN.	1 s MAX.
b	_	100 ns MAX.
c	50 ms MIN.	-
d	-	10 ms MAX.

	POWER OFF	
Symbol	Allowable value	
е	0 ms MIN.	1 s MAX.
f	0 ms MIN.	1 s MAX.
g	15 ms MIN.	_

- (NOTE 1) Power ON/OFF cycle time. All signals and power line shall be in accordance with above sequence in case of power ON/OFF.
- (NOTE 2) Before DISP rise up, the signals of YD,LP,XCK,DATA and M must be input, and the above condition of "a" must be satisfied. The signals which comply with the interface timing in Fig.5,Fig.6, and table 8, must be input.



# SPECIFICATIONS ARE SUBJECT TO CHANGE WITHOUT NOTICE.

Suggested applications (if any) are for standard use; See Important Restrictions for limitations on special applications. See Limited Warranty for SHARP's product warranty. The Limited Warranty is in lieu, and exclusive of, all other warranties, express or implied. ALL EXPRESS AND IMPLIED WARRANTIES, INCLUDING THE WARRANTIES OF MERCHANTABILITY, FITNESS FOR USE AND FITNESS FOR A PARTICULAR PURPOSE, ARE SPECIFICALLY EXCLUDED. In no event will SHARP be liable, or in any way responsible, for any incidental or consequential economic or property damage.



### **NORTH AMERICA**

SHARP Microelectronics of the Americas 5700 NW Pacific Rim Blvd. Camas, WA 98607, U.S.A. Phone: (1) 360-834-2500 Fax: (1) 360-834-8903

Fast Info: (1) 800-833-9437 www.sharpsma.com

### **TAIWAN**

SHARP Electronic Components (Taiwan) Corporation 8F-A, No. 16, Sec. 4, Nanking E. Rd. Taipei, Taiwan, Republic of China Phone: (886) 2-2577-7341

Fax: (886) 2-2577-7326/2-2577-7328

# **CHINA**

SHARP Microelectronics of China (Shanghai) Co., Ltd. 28 Xin Jin Qiao Road King Tower 16F Pudong Shanghai, 201206 P.R. China Phone: (86) 21-5854-7710/21-5834-6056 Fax: (86) 21-5854-4340/21-5834-6057 **Head Office:** 

No. 360, Bashen Road, Xin Development Bldg. 22 Waigaoqiao Free Trade Zone Shanghai 200131 P.R. China Email: smc@china.global.sharp.co.jp

### **EUROPE**

SHARP Microelectronics Europe Division of Sharp Electronics (Europe) GmbH Sonninstrasse 3 20097 Hamburg, Germany Phone: (49) 40-2376-2286 Fax: (49) 40-2376-2232

### **SINGAPORE**

www.sharpsme.com

SHARP Electronics (Singapore) PTE., Ltd. 438A, Alexandra Road, #05-01/02 Alexandra Technopark, Singapore 119967 Phone: (65) 271-3566 Fax: (65) 271-3855

# HONG KONG

SHARP-ROXY (Hong Kong) Ltd. 3rd Business Division, 17/F, Admiralty Centre, Tower 1 18 Harcourt Road, Hong Kong Phone: (852) 28229311 Fax: (852) 28660779 www.sharp.com.hk

# **Shenzhen Representative Office:**

Room 13B1, Tower C, Electronics Science & Technology Building Shen Nan Zhong Road Shenzhen, P.R. China

Phone: (86) 755-3273731 Fax: (86) 755-3273735

### **JAPAN**

**SHARP Corporation** Electronic Components & Devices 22-22 Nagaike-cho, Abeno-Ku Osaka 545-8522, Japan Phone: (81) 6-6621-1221 Fax: (81) 6117-725300/6117-725301

www.sharp-world.com

### **KOREA**

SHARP Electronic Components (Korea) Corporation RM 501 Geosung B/D, 541 Dohwa-dong, Mapo-ku Seoul 121-701, Korea Phone: (82) 2-711-5813 ~ 8

Fax: (82) 2-711-5819